BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/OW/WORK_INDENT18383/CALL-2

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Maintenance of BBMP Drilled Borewells in Ward No. 09 vidyaranyapura sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of R MADHUSUDAN		
				In Figures		In Words
1	32	Lifting of Submersible pump set as per Soecification and direction etc., complete and as per the directions of the Engineer-in-charge of the work	Each	850.0	27200.00	Rupees Eight Hundred Fifty Only
2	32	Transportation of pumping machineries etc., complete and as per the directions of the Engineer-in-charge of the work	Each	900.0	28800.00	Rupees Nine Hundred Only
3	32	Labour charges (over hauling) etc., complete and as per the directions of the Engineer-in-charge of the work	Job	550.0	17600.00	Rupees Five Hundred Fifty Only
4	32	A) Repairs to Motor: Rewinding of submersible pump sets with copper insulation wire of suitable gauge as per ISI specification with guarantee of 6 months. (Above 10 HP upto 20 HP add Rs.150/- for every HP) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	4750.0	152000.00	Rupees Four Thousand Seven Hundred Fifty Only
5	32	Starter (with one year Guarantee) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	5050.0	161600.00	Rupees Five Thousand Fifty Only
6	32	Rotor (with one year Guarantee) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	4700.0	150400.00	Rupees Four Thousand Seven Hundred Only
7	32	Upper Flange etc., complete and as per the directions of the Engineer-in-charge of the work	No.	350.0	11200.00	Rupees Three Hundred Fifty Only
8	32	Lower Housing etc., complete and as per the directions of the Engineer-in-charge of the work	No.	650.0	20800.00	Rupees Six Hundred Fifty Only
9	32	Carbon Housing etc., complete and as per the directions of the Engineer-in-charge of the work	No.	475.0	15200.00	Rupees Four Hundred Seventy Five Only
10	32	Thrust bearing block assembly complete with Segment bearing pad etc., complete and as per the directions of the Engineer-in-charge of the work	No.	1150.0	36800.00	Rupees One Thousand One Hundred Fifty Only
11	32	Oil Seal etc., complete and as per the directions of the Engineer-in-charge of the work	No.	125.0	4000.00	Rupees One Hundred Twenty Five Only
12	32	Oil Seal Steel Bush etc., complete and as per the directions of the Engineer-in-charge of the work	No.	150.0	4800.00	Rupees One Hundred Fifty Only
13	510	Guide vane etc., complete and as per the directions of the Engineer-in-charge of the work	No.	175.0	89250.00	Rupees One Hundred Seventy Five Only
14	510	Impeller Shell moulded with aluminium Bronze) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	405.0	206550.00	Rupees Four Hundred Five Only
15	32	Discharge outlet (D.O) Bearing D.O Steel Bush etc., complete and as per the directions of the Engineer-in-charge of the work	No.	445.0	14240.00	Rupees Four Hundred Forty Five Only
16	32	Steel Bush etc., complete and as per the directions of the Engineer-in-charge of the work	No.	150.0	4800.00	Rupees One Hundred Fifty Only
17	32	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	850.0	27200.00	Rupees Eight Hundred Fifty Only
18	32	Non – return valve (NRV) assembly complete with rubber 'O' Ring etc., complete and as per the directions of the Engineer-in-charge of the work	No.	1050.0	33600.00	Rupees One Thousand Fifty Only
19	32	Cable Guard etc., complete and as per the directions of the Engineer-in-charge of the work	No.	150.0	4800.00	Rupees One Hundred Fifty Only
20	32	Brass Filter etc., complete and as per the directions of the Engineer-in-charge of the work	No.	250.0	8000.00	Rupees Two Hundred Fifty Only
21	32	Re-erection charges of pumping machineries including overhauling and pointing etc., complete and as per the directions of the Engineer-in-charge of the work	Each	950.0	30400.00	Rupees Nine Hundred Fifty Only

30/3/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of R MADHUSUDAN		
				In Figures		In Words
22	100	Supplying of ISI marked galvanized mild steel tube (continously welded electric resistance welded (ERW) high frequency, induction welded (HFIW) Hot finished welded type of nominal bore given below screwed at both ends as per IS 554/1986 with latest amendments, pipes threaftes at one end and the other end protected asper specification in random lengths of 4 to 7 mtrs Confirming to IS 1239 part I/1990 with amendament 1-5 and with all its latest amendements if any. The pipes supplied should be with BIS mark etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	355.0	35500.00	Rupees Three Hundred Fifty Five Only
23	30	Heavy Duty Collar 50 mm dia etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	130.0	3900.00	Rupees One Hundred Thirty Only
24	300	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	135.0	40500.00	Rupees One Hundred Thirty Five Only
25	50	Supplying of LTUG cable having aluminium condutor PVC insulated shethed, galvnised steel, wire / steel tap armoured cable with PVC outer sheathing 1.1 KV class.P No. 68/ I No. 4(d) 4 core 16 Sqmm etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	140.0	7000.00	Rupees One Hundred Forty Only
26	50	Labour charges for laying of 1.1 K.V class UG cable (PWD Electrical SR-1999-2000, P No. 69 / I No. Ia In existing trencg/duct 6Sqmm to 16 Sqmm) etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	10.0	500.00	Rupees Ten Only
27	40	Digging or trenching of 0.6m deep x 0.5 mtr wide refilling the trench to the required ground level and consolidating etc., complete (as per Civil SR KSRB 1-2 P-7) etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	85.0	3400.00	Rupees Eighty Five Only
28	20	Supplying and fixing of Class A (meaium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	345.0	6900.00	Rupees Three Hundred Forty Five Only
29	8	Supplying and fixing L.T. cast Iron pot head suitable for 1.1 KV class UG cable filled with necessary bituumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., complete and as per the directions of the Engineer-in-charge of the work	No.	280.0	2240.00	Rupees Two Hundred Eighty Only
30	120	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete and as per the directions of the Engineer-in-charge of the work	No.	170.0	20400.00	Rupees One Hundred Seventy Only
31	8	Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	1579.0	12632.00	Rupees One Thousand Five Hundred Seventy Nine Only
32	4	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spotetc., complete and as per the directions of the Engineer-in-charge of the work	No	227.0	908.00	Rupees Two Hundred Twenty Seven Only

30/3/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of R MADHUSUDAN		
				In Figures		In Words
33	351000	Fabrication supplying and mounting MS box of 16 SWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primer paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 sqcm @ Rs.0.33 etc., complete and as per the directions of the Engineer-in-charge of the work	Sq.Cm	0.18	63180.00	and Eighteen Paise Only
34	180	Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including shiriry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strructure manhole. etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	150.0	27000.00	Rupees One Hundred Fifty Only
35	400	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	105.0	42000.00	Rupees One Hundred Five Only
36	180	Refilling the basement and pipeline treanches with secleted available earthe for trench excavation including authority condition in layers from thedi including disponsary of the sunplus earth with a heavy 200 mtrs etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	51.0	9180.00	Rupees Fifty One Only
37	24	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments etc., complete and as per the directions of the Engineer-in-charge of the work	Each	1265.0	30360.00	Rupees One Thousand Two Hundred Sixty Five Only
					1354840.00	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

30/3/16

30/03